



Management Project

Mold & Co in China

Marie CHIAVERINI Baptiste SACLIER
Vadim CROCHET Antoine CAILLET
Romain JUNCA

Table of contents

1	Introduction	4
2	Project description	4
2.1	Specifications	5
2.2	Forces	6
2.3	Weaknesses	6
3	Actors and Stakeholders	6
4	Project planning	7
5	Required resources	8
6	Risks management	9
7	Indicators of progression and success	10
8	Conclusion	11

List of figures

Introduction

This document describes all aspects of the ChineseTooth project which the main goal is to install IT systems around the new production line in the eco-city of Taijin. This project includes a social and ecological aspect in order to fit to the requirements of Taijin city guidelines.

In this document, we describe what are the goals, the processes, the planning and the risk of such deployment in China.

Project description

The main goal is to install a toothbrush production line in the eco-city of Taijin in China. Our company is working for MOLD & Co. to make this production line a reality.

Our main guidelines in this project is to install a production line that can produce a great amount of toothbrushes within an eco-city. This project needs to be respectful of the surrounding environment and social aspects of the project's stakeholders.

2.1 Specifications

This project has to achieve the following specifications.

The production line must contain all the required machines to automate the production of toothbrushes. These machines include moulting machine, stamping machine, tufting machine, bristle cutter machine, bristle trimming machine and Packaging machine. These machines need to be bought and connected to each other in order to build the full product.

To connect all the machines in the assembly line, the project requires also a full digital connection to an internal network. This network groups all connected machines and database servers to store monitoring informations about the production. These informations need to represent the current production, the past production and potential errors in the production line.

The production line is fully automated through this network and the production is regulated to produce exactly what is needed. This automation brings many advantages including the environmental impact reduction, reduction of the storage requirement of finished products and 24/7 production in case of huge demand.

The informations collected need to be displayed to the employees in charge of the production line. These informations are displayed through an interface reading the monitoring data from the database. A master server has to be installed in order to control all machines and to control the production flow.

Several materials are required to produce toothbrushes. These materials are plastic, nylon, brass wire, paper box packing, plastic hard container packaging, high frequency blister packaging and Blister card packaging. The project must include a storage space for all these materials and human resources to load the resources in the appropriate machines.

All the production line machines, storage and digital network requires engineering to organise all these components depending on the space available and the shape of the building. Engineering human resources are required to create, configure and install monitoring system. Human resources may also be required to manipulate machines, connect

each machine to the other and install network.

2.2 Forces

The forces of the project are mainly focused on the high efficiency of the production line. This high efficiency is guaranteed by the monitoring system and the automatic management of the amount of product produced on the assembly line. This project represents a great opportunity to modernize the production of MOLD & Co. and automate the assembly line. By automating the assembly line, MOLD & Co. gain a lot of money on storage of manufactured products and human resources.

2.3 Weaknesses

This project have also small weakness that may have an impact on risks (Risk management will be covered in the section 6).

The main weakness are the important amount of advanced technologies that requires a great amount of high qualified employees in charge of the installing and maintaining the autonomous system of the assembly line. Another weakness is the requirement of heavy and pricy machines that can represent a major part of the project's costs.

Actors and Stakeholders

Project planning

Required resources

Risks management

Indicators of progression and success

Conclusion